

---

# Investigation of Inter- and Intra-Chain Interactions in Mixtures of Long-Chain Polymer Monomer with Relations to Applications in agriculture of Plant Cuticular Waxes: Using n-Nonadecane and 1-Octadecanol Mixture as example

---

Wentao Guo , [Yi Xing](#) , [Wei Wen](#) <sup>\*</sup> , [Wei Su](#) <sup>\*</sup> , Changjiang Hou , Guotao Li , Lyumeng Ye

Posted Date: 11 March 2024

doi: 10.20944/preprints202403.0628.v1

Keywords: Organics; Crystallization; Binary system; Phase transition; Thermodynamics; Long-Chain Polymer Monomer.



Preprints.org is a free multidiscipline platform providing preprint service that is dedicated to making early versions of research outputs permanently available and citable. Preprints posted at Preprints.org appear in Web of Science, Crossref, Google Scholar, Scilit, Europe PMC.

Copyright: This is an open access article distributed under the Creative Commons Attribution License which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Disclaimer/Publisher's Note: The statements, opinions, and data contained in all publications are solely those of the individual author(s) and contributor(s) and not of MDPI and/or the editor(s). MDPI and/or the editor(s) disclaim responsibility for any injury to people or property resulting from any ideas, methods, instructions, or products referred to in the content.

Article

# Investigation of Inter- and Intra-Chain Interactions in Mixtures of Long-Chain Polymer Monomer with Relations to Applications in agriculture of Plant Cuticular Waxes: Using n-Nonadecane and 1-Octadecanol Mixture as Example

Wentao Guo <sup>1</sup>, Yi Xing <sup>1</sup>, Wei Wen <sup>1,\*</sup>, Wei Su <sup>1,\*</sup>, Changjiang Hou <sup>2</sup>, Guotao Li <sup>2</sup> and Lyumeng Ye <sup>3</sup>

<sup>1</sup> School of Energy and Environmental Engineering, University of Science and Technology Beijing, Beijing 100083, China; wentao\_guo@ustb.edu.cn; xingyi@ustb.edu.cn; wenwei@ustb.edu.cn; suwei@ustb.edu.cn

<sup>2</sup> Group Strategic Research Institute, HBIS Group Co., Ltd, Shijiazhuang, Hebei, 050023, China; houchangjiang@hbisco.com; otao@hbisco.com

<sup>3</sup> Guangdong Province Engineering Laboratory for Air Pollution Control, South China Institute of Environmental Sciences, the Ministry of Ecology and Environment of PRC. Guangzhou 510655, China.; yelvmeng@scies.org

\* Correspondence: wenwei@ustb.edu.cn, suwei@ustb.edu.cn

**Abstract:** The article delves into the intricate phase transitions of 1-Octadecanol and n-Nonadecane within a binary system, unveiling dynamic structural changes under varying conditions. Through Fourier-transform infrared (FTIR) analysis, specific molecular vibrations were identified, shedding light on the molecular composition and interactions. The study highlights the challenges in detecting subtle phase transitions and emphasizes the individuality of molecular behaviours in closely related compounds. The findings underscore the complexity of phase transitions in binary systems and advocate for a nuanced approach to studying molecular structures and behaviours. Additionally, the research contributes valuable insights into the molecular dynamics of Organic Polymer Functional Adsorption Materials, offering implications for synthetic waxy layers in plant epidermis.

**keywords:** organics; crystallization; binary system; phase transition; thermodynamics; long-chain polymer monomer

## 1. Introduction

### 1.1. Research Backgrounds

Agriculture is one of the most important primary industries in the world today and a vital prerequisite for supporting the most basic livelihoods in all countries and regions. In almost all plants with large leaves (non-coniferous species), the leaves are one of most indispensable parts of the plants [1]. We know that leaves contain chloroplasts, which absorb sunlight for photosynthesis and provide energy for the plant, and cuticles, which regulate the internal and external osmotic pressure and keep the water in the leaves at a healthy level.

According to current research, there is no direct link between plant cuticle wax and osmosis, and this paper is an attempt to establish the relationship between the two; abiotic stresses are also one of the critical issues for plants to survive long terms, such as Heat, Drought, Metals, Cold, Salt and Flooding [2]. How plants survive such abiotic stresses is not yet clear [3]. At the same time, improving crop yields is a global problem, and many scholars have conducted in-depth research on crop yield improvement through physical, chemical, biological, and geographical aspects. This project's results will significantly help improve crop performance, for example, this project's results will greatly help

improve crop performance, for example, by optimizing plant cuticle waxes through genetic engineering or other means. In addition, the cuticle wax will act as a protective measure for the plant epidermis, blocking growth-aiding agrochemicals from being sprayed [4]. The agrochemicals can be designed to work around this protective layer by studying this project. In addition, this is a process of chemically creating a distinct biomimetic plant surface that can be applied to, for example, biology or other disciplines.

### 1.2. Plant Cuticle Waxes

The transition of land plants from an aquatic to a terrestrial lifestyle was accompanied by the development of a novel structure known as the cuticle [4,13]. This lipophilic layer, composed of cutin and cuticular waxes, had the primary purpose of limiting water loss that was not caused by stomata by acting as a physical barrier between the surface of the plant and the environment outside of the plant [5,6,14]. Forming a cuticular wall is one of the primary adaptation strategies that allow plants to survive and thrive in water-restricted terrestrial environments [7,8,15]. The cuticle protects the plant from mechanical rupture or injury, poisonous chemicals, and ultraviolet radiation [9,10,14]. It serves as the primary barrier between the aerial surface of plants and the external environment. The cuticle also plays essential roles in the processes of growth and development, such as avoiding epidermal fusion by establishing appropriate organ borders [11,13] and maintaining phytohormone homeostasis [2,12]. These are only two examples of these roles. It is well known that the cuticle and the components that make up the cuticle perform essential roles as signaling molecules for pathogens that attack plants and the plants themselves [16]. It also plays a significant function in fruits, affecting quality, defense, and shelf life after harvest [13]. In fruits, the cuticle can affect water retention, hardness [14,17], and reactions to both biotic and abiotic stressors.

There is much research on plant wax globally, and the understanding of its composition is also more profound. Plant epidermal wax is a mixture of hydrophobic organic substances that appear as a whitish-grey or greenish-grey frost covering the outer layers of epidermal plant cells. Waxes are not unique to plant leaves, but studies on waxes have been mainly focused on plant leaves. The chemical composition of waxes is mixed, and the chemical substances in waxes can be extracted effectively with organic solvents such as trichloromethane ( $\text{CHCl}_3$ ). Modern studies primarily rely on gas chromatography-mass spectrometry (GC-MS) and nuclear magnetic resonance (NMR) techniques to identify wax components, and more than 100 compounds have been identified. The chemical features of waxes mainly include aliphatic compounds and cyclic compounds. Aliphatic compounds include long-chain (larger than  $\text{C}_{18}$ ) and ultra-long-chain ( $\text{C}_{24}$ - $\text{C}_{36}$ ) fatty acids, alkanes, alcohols, aldehydes, ketones, and esters, with different odd-even state advantages. Ring compounds contain phenols, terpenoids and flavonoids, and some of them are small molecular secondary metabolites of plants. The form and content of plant cuticle varies greatly across and within species and includes plate-, needle-, and pillar-shaped wax crystals. This variation is to be anticipated given the diversity of plants, the ecosystems they occupy, and the unique life histories of individual plants [15]. In certain species, the composition of the cuticular wax is known to change with increasing depth, resulting in the formation of layers that may be chemically differentiated [18]. In addition, the cuticle has been demonstrated to have a crucial role in both the development and the pathophysiology of diseases [18, 19, 20, 21, 22, 23, 24]. It should not come as a surprise, therefore, that interest in the content, structure, and physiology of cuticles is growing [14, 24, 25, 26]. A better understanding of the relationship between the structure and the chemical composition of cuticle waxes (and its relation to Inter- and Intra-Chain Interactions in Mixtures of Long-Chain Hydrocarbons) is essential for increasing agricultural yields. This is because it will further our knowledge of how plants regulate water balance and inform the application of nutrition (foliar feeds) and pesticides, which will lead to improved formulation strategies for agrochemicals. Moreover, agriculture yields can be increased by Therefore, a knowledge of the inter- and intra-chain interactions in mixtures of long-chain hydrocarbons, in connection to plant cuticular waxes, can give a leading niche to the fulfilment of the protection and future investigations into a more effective cuticular protection component.

According to recent research, the major transpiration barrier is formed by intra-cuticular waxes, and the contribution of the epi-cuticular waxes as a transpiration barrier varies on the makeup of the cuticle of each species. And also, intra-cuticular wax acts as a transportational barrier [17].

### 1.3. Approaching

This study's primary goal was to create a model of plant leaf intra-cuticular wax that could be used to calculate the effects of formulations on cuticle stresses. The model should be as straightforward and uncomplicated as is practicable, but it should also retain some essential characteristics of the cuticular membrane that has been removed (such as response to changes in ambient conditions and susceptibility to the use of surfactants and solvents as adjuvants).

## 2. Materials and Methods

### 2.1. Mass Calculation

Twenty-one samples were made at the beginning of the experiment. The samples were differenced by 5% each. All the samples were thoroughly mixed to confirm they were in equilibrium. Then crush the sample into powder since all the analysis methods are using fine powder for the analysis.

The desired weight size of each sample was around 30-40 milligrams.

The total molar weight is:

$$M_{total} = \sum mole\% \times M \quad (3.1)$$

The weight percentage of each chemical is:

$$Wt\% = \frac{mole\% \times M}{M_{total}} \quad (3.2)$$

The mass of each chemical for making the samples is:

$$Mass(g) = Wt\% \times 20 \quad (3.3)$$

The compositions of samples(mol%) we prepared are listed in Tables 1 and 2:

**Table 1.** The Chemicals information of each sample.

Sample No.	Molar fraction (C <sub>18</sub> OH/C <sub>19</sub> )	n-Nonadecane mass (g)	1-Octadecanol mass (g)	Total mass (g)
1	0	0	0.03	0.03
2	5	0.001923	0.037107	0.03903
3	10	0.003846	0.035154	0.039
4	15	0.005769	0.033201	0.03897
5	20	0.007692	0.031248	0.03894
6	25	0.009615	0.029295	0.03891
7	30	0.011538	0.027342	0.03888
8	35	0.013461	0.025389	0.03885
9	40	0.015384	0.023436	0.03882
10	45	0.017307	0.021483	0.03879
11	50	0.01923	0.01953	0.03876
12	55	0.021153	0.017577	0.03873
13	60	0.023076	0.015624	0.0387
14	65	0.024999	0.013571	0.03857
15	70	0.026922	0.011718	0.03864
16	75	0.028845	0.009765	0.03861
17	80	0.030768	0.007812	0.03858
18	85	0.032691	0.005859	0.03855
19	90	0.034614	0.003906	0.03852

20	95	0.036537	0.001953	0.03849
21	100	0.03	0	0.03

**Table 2.** The crucible weight and sample weight for Reproducibility (in crucible).

Sample No.	Molar fraction (C <sub>18</sub> OH/C <sub>19</sub> )	Crucible weight (empty)/mg	Crucible weight (full)/mg	Sample weight (mg)
Re-1 (1)	0	48.38	58.07	9.69
Re-1 (11)	50	48.63	58.54	9.91
Re-1 (21)	100	48.43	56.57	8.14
Re-2 (1)	0	48.26	56.19	7.93
Re-2 (11)	50	48.59	55.06	6.47
Re-2 (21)	100	49.19	59.61	7.93

## 2.2. Data Collection and Analysis

### 2.2.1. DSC

The Differential Scanning Calorimetry (DSC) instrument was used to investigate the long chain hydrocarbons' thermal properties. These properties included the phase change enthalpy, melting and solidification temperature and total enthalpy. For the purposes of the measurements, the instrument was calibrated using internal standards crucible made of Aluminum. The DSC measurements were carried out in an inert N<sub>2</sub> environment with a heating-cooling rate of 1°C min<sup>-1</sup> throughout a temperature range of 20 to 70 degrees Celsius. Putting each crucible in the specific place on the pan holder, record the name of each sample, position on the holder, then set the method of this analysis (cooling and heating rate), input the empty weight of crucible which sample in and the weight of reference crucible, in this case, the weight of reference crucible was 49.000mg. Finally, sent the experiment to the instrument and run it for analysis.

The method of DSC used during this project was a heatwave-type, and the heating and cooling rate for major experiments was 1°C per minute and a 3-time repeat. This step was designed to analyze the fusion and crystallization process of the samples. And using different rate which was 0.75 and 0.5 °C per minute for further analysis.

Using STAR<sup>e</sup> software to analyze the collected DSC diagrams, displaying the Onset Temperature, End set Temperature, and Peak Temperature, then integrating the peaks, getting the area of each peak, and shading the peak area.

### 2.2.2. FTIR

Utilizing Fourier transform infrared (FT-IR) spectroscopy, long-chain hydrocarbons were chemically characterized. Between 4000 and 400 cm<sup>-1</sup>, a NICOLET iS10 produced by Thermo-Scientific was utilized for the FT-IR analyses. There was a crystal on the surface of the FTIR instrument. An environment diagram was analyzed before the experiment. Then the sample powder covered the crystal completely during the experiment. Then the samples were analyzed by operating the computer, and the diagram of the sample was shown on the screen of the PC.

Using OriginLab<sup>®</sup> for plotting the Infrared spectra after getting the raw data from the FTIR instrument. Then Analysis the wavenumber of the peaks and get different vibration types of each sample.


## 3. Results

This section may be divided by subheadings. It should provide a concise and precise description of the experimental results, their interpretation, as well as the experimental conclusions that can be drawn.

### 3.1. DSC Diagrams


#### 3.1.1. Cooling rate at 1°C/min

The cooling Differential Scanning Calorimetry (DSC) diagram for heating and cooling cycle 1, conducted at a rate of 1°C/min, reveals a nuanced profile with a maximum of four peaks and a minimum of two peaks. The dynamic nature of the peaks is closely tied to the evolving composition during the process. Notably, the rightmost peak signifies the crystallization of 1-Octadecanol from the liquid phase into a rotator phase. Following this, the subsequent peak denotes the transition of 1-Octadecanol from the rotator phase to an ordered phase. On the left side of the spectrum, attention is drawn to the two peaks related to n-Nonadecane. The rightward of these depicts the crystallization of n-Nonadecane from the liquid phase into a rotator phase, while the leftward peak marks the transition of the rotator-phase-n-Nonadecane into an ordered phase. The shifting positions of these peaks as the composition undergoes alterations provide valuable insights into the intricate thermodynamic transformations occurring within the substance, offering a comprehensive understanding of its phase transitions and crystallization behaviour during the specified heating and cooling cycle [27].




**Figure 1.** Cooling Phase diagram at 1°C/min (Cycle 1).


Presented below are comprehensive Differential Scanning Calorimetry (DSC) diagrams recorded at a scan rate of 1 degree Celsius per minute (1°C/min). The upper trio of diagrams illustrates the cooling phase, providing a detailed exploration of the thermal transitions occurring in the material under decreasing temperatures. Conversely, the subsequent set of diagrams captures the heating phase, shedding light on the reverse process as the material warms up. This collection of DSC diagrams serves as a meticulous representation of the thermal behaviour, elucidating key transformations and transitions that unfold within the substance across varying temperature ranges. The cooling diagrams offer insights into the solidification and crystallization processes, while the heating diagrams unveil the corresponding melting events and other thermal phenomena, collectively contributing to a comprehensive understanding of the material's thermal characteristics.



**Figure 2.** Cooling(a) and Heating(b) Phase diagram at 1°C/min (Cycle 1).



**Figure 3.** Cooling(a) and Heating(b) Phase diagram at 1°C/min (Cycle 2).




**Figure 4.** Cooling(a) and Heating(b) Phase diagram at 1°C/min (Cycle 3).

The analysis of the thermal behaviour presented in the comparison of the three cycles, each conducted at a constant cooling and heating rate of 1°C per minute, reveals a remarkable consistency. In observing the Specific DSC diagram provided below, the cooling and heating segments are visually distinguishable. The blue portion signifies the cooling procedure of the sample, while the red part corresponds to the heating phase. Notably, despite the dynamic transitions in temperature, the absence of discernible differences in the cooling and heating rates across the three cycles indicates an exceptional level of stability exhibited by the samples.

Delving deeper into the intricacies of the analysis, attention is drawn to the significance of the peaks within the DSC diagram. These peaks encapsulate critical information about the sample's behaviour during phase transitions. By integrating the area under each peak, we gain valuable insights into the enthalpy associated with each specific phase transition. This approach allows for a nuanced understanding of the energy changes occurring within the sample, providing a comprehensive perspective on its thermal properties. In essence, the Specific DSC diagram serves as a visual representation of the stability and thermodynamic characteristics of the material under

investigation, elucidating the subtleties of its responses to varying temperature conditions. For instance, the Differential Scanning Calorimetry (DSC) profile of pure 1-Octadecanol, as depicted in Figure 5 using STAR<sup>e</sup> software, was obtained under specific experimental conditions. These conditions included a heating rate of 1°C per minute and a corresponding cooling rate. Within this diagram, the blue segment illustrates the exothermic reaction phase of 1-Octadecanol, whereas the red segment delineates its endothermic reaction phase. Two tables of Phase transition temperature and enthalpy value of each peak (Tables 3 and 4) was obtained by concluding all DSC diagram.



**Figure 5.** An example of DSC diagram in STAR<sup>e</sup> software (pure 1-Octadecanol) Note: (■) Exothermic reaction phases of 1-Octadecanol, (■) Endothermic reaction phases.

**Table 3.** Comparison of Transition Enthalpy between the Experimental Results and the Mean Values of the Literature.

C <sub>n</sub>	Molar Mass (g/mol)	T <sub>m</sub> (K)	ΔH <sub>m</sub> (kJ/mol)	T <sub>R-C</sub> (K)	ΔH <sub>R-C</sub> (kJ/mol)	ΔH <sub>total</sub> (kJ/mol)	Reference
18	270.49	330.3	-	328.00	-	-	Miquel Àngel, 2021 [28]
		328.2	44.742	321.78	15.756	60.498	This study
		304.9	45.580	295.5	13.750	59.330	Dirand et al., 2002 [27]
19	268.52	305.1	46.047	294.5	13.801	59.848	Cholakova et al., 2019 [29]
		303.6	31.417	294.2	9.134	40.551	This study

**Table 4.** Comparison of Different Compositions between 1-Octadecanol and n-Nonadecane.

Composition (C <sub>18</sub> OH %)	M <sub>w</sub> (g/mol)	T <sub>m</sub> (K)	ΔH <sub>m</sub> (kJ/mol)	T <sub>R-γ</sub> (K)	ΔH <sub>R-γ</sub> (kJ/mol)	T <sub>L-RI</sub> (K)	ΔH <sub>L-RI</sub> (kJ/mol)	T <sub>R-Oi</sub> (K)	ΔH <sub>R-Oi</sub> (kJ/mol)	ΔH <sub>total</sub> (kJ/mol)
0	268.5200	303.60	9.134	-	-	301.79	31.417	-	-	40.551
5	268.6185	305.02	7.211	-	-	301.89	31.093	-	-	38.304
10	268.7170	308.33	3.727	-	-	302.03	28.532	290.27	6.909	39.168
15	268.8155	316.75	4.449	-	-	301.71	27.107	290.18	6.804	38.36
20	268.9140	318.38	6.868	-	-	301.81	26.061	290.30	6.4619	39.391
25	269.0125	319.15	8.248	-	-	301.97	24.074	290.21	5.617	37.939
30	269.1110	319.62	9.368	-	-	301.86	22.662	290.11	5.253	37.283
35	269.2095	321.05	11.853	-	-	301.91	21.542	289.87	4.937	38.332
40	269.3080	321.55	13.024	-	-	301.84	21.203	289.69	4.551	38.778
45	269.4065	322.61	13.899	-	-	301.80	18.306	1289.83	3.483	35.688
50	269.5050	323.3	15.669	305.48	2.647	301.87	15.402	289.98	3.339	37.057
55	269.6035	324.42	17.565	307.68	4.341	302.02	13.270	290.07	2.879	38.055
60	269.7020	325.25	18.127	309.11	5.453	302.09	11.373	289.97	2.368	37.321


65	269.8005	325.62	19.431	310.47	6.904	302.07	10.279	289.78	1.983	38.597
70	269.8990	326.41	20.569	312.95	9.471	302.15	8.461	289.16	1.636	40.137
75	269.9975	326.55	19.872	313.68	9.080	302.14	5.989	289.91	1.237	36.178
80	270.0960	327.27	21.454	315.56	11.590	302.11	4.303	-	-	37.347
85	270.1945	328.26	21.983	317.07	13.839	302.04	3.132	-	-	38.954
90	270.2930	328.42	22.891	318.07	13.836	-	-	-	-	36.727
95	270.3915	329.6	26.114	320.77	15.407	-	-	-	-	41.521
100	270.4900	329.86	44.742	321.85	15.756	-	-	-	-	60.498

### 3.1.2. Cooling Rate at 0.75°C/min and 0.5°C/min


The DSC (Differential Scanning Calorimetry) diagrams depicting various cooling or heating rates for sample No.11 with a composition of 50% n-Nonadecane and 50% 1-Octadecanol are illustrated through Figures 6–8. Notably, the altitude of the peaks exhibited a decreasing trend as the rate of cooling or heating diminished. This phenomenon is attributed to the profound influence of the temperature ramp rate on resolution and sensitivity during sample analysis.

In general, a faster rate of temperature increases results in lower resolution and higher sensitivity, while a slower rate contributes to higher resolution and lower sensitivity. As the ramp rate escalates, the onset temperature of the melt peak remains relatively stable, but the peak top and end temperatures rise, leading to a broader peak shape. Rapid ramp-up processes tend to induce superimposed thermal effects, causing inadequate separation of individual peaks or melts associated with different phases.


Conversely, during the cooling phase, the rate influences the crystallization behaviour. A swift cooling rate tends to delay crystallization, yet this method proves advantageous in optimizing product processing. Notably, the overall peak shape at varying rates closely resembled the diagram obtained at a consistent rate of 1°C/min. This consistency implies that the sample utilized for diverse rate scanning exhibited stability. Consequently, it can be inferred that all samples share a common stability, contributing to a comprehensive understanding of the thermodynamic behaviour and phase transitions in the tested mixtures.



**Figure 6.** Differential Scanning Calorimetry (DSC) diagram at cooling(a)/ heating(b) different rates (1,0.75,0.5°C/min, Cycle 1), Note: (■): 1, (■): 0.75, (■): 0.5.




**Figure 7.** Differential Scanning Calorimetry (DSC) diagram at cooling(a)/ heating(b) different rates (1,0.75,0.5°C/min, Cycle 2), Note: (■): 1, (■): 0.75, (■): 0.5.



**Figure 8.** Differential Scanning Calorimetry (DSC) diagram at cooling(a)/ heating(b) different rates (1, 0.75, 0.5°C/min, Cycle 3), Note: (■): 1, (■): 0.75, (■): 0.5.

### 3.1.3. Reproducibility

The reproducibility of the experiment was a crucial aspect of our investigation, and rigorous measures were taken to ensure the reliability of the results. To assess this, three separate samples were independently run at 1dCpm, each undergoing two additional repetitions. The obtained data was meticulously analyzed, and the corresponding chromatograms were compared. The resulting chromatograms, as depicted in Figure 9, revealed a striking similarity in both the shape and height of the peaks across all replicates. In fact, the resemblance was so pronounced that the chromatograms appeared almost identical. This remarkable consistency in the patterns observed strongly indicates that the experiment was highly reproducible. The reliable replication of results not only attests to the robustness of our methodology but also instills confidence in the credibility and accuracy of the findings derived from this experimental setup.



**Figure 9.** Reproducibility Differential Scanning Calorimetry (DSC) diagram (1°C/min) with different compositions; (a) 1-Octadecanol 0% / n-Nonadecane 100%; (b) 1-Octadecanol 50% / n-Nonadecane 50%; (c) 1-Octadecanol 100% / n-Nonadecane 0%. Note: (■): Samples in Table 1, (●): 1<sup>st</sup> Reproduction, (●): 2<sup>nd</sup> Reproduction.

### 3.2. Phase Diagram

#### 3.2.1. Cooling Phase Diagram

The construction of a binary system phase diagram involved a meticulous analysis of the DSC (Differential Scanning Calorimetry) diagram, where the peak temperatures were systematically summarized. This comprehensive diagram serves as a visual representation of the intricate phase transitions occurring within the constituent materials. Each segment of the binary system is distinctly depicted, allowing for a nuanced understanding of the thermodynamic behaviour.

Upon careful examination of the phase diagram, a significant observation emerges: the absence of any discernible evidence pointing towards Eutectic or Peritectic reactions. Eutectic reactions typically involve the simultaneous solidification of two or more phases from a liquid, while Peritectic reactions entail the transformation of one solid phase into another. The lack of indicators for these reactions in the diagram underscores the stability and unique characteristics of the binary system under consideration.


In essence, the plotted phase diagram not only elucidates the temperature-dependent transitions within the binary system but also provides crucial insights into the absence of specific reactions that might alter its composition or structure. This analytical approach not only enhances our understanding of the thermodynamic behaviour of the materials involved but also contributes to the broader field of materials science by unraveling the intricate interplay of phases within binary systems.

In the thermal journey from elevated temperatures to lower ones, the dynamic transformations of 1-Octadecanol exhibit a sequence of phases. Initially existing in a liquid state, it undergoes a transition to the R'IV phase, characterized by specific structural arrangements. As the temperature further decreases, the 1-Octadecanol experiences another shift in its molecular organization, entering the Monoclinic ( $\gamma$ ) phase. This progression signifies the intricate interplay of molecular forces and interactions within the substance as it responds to variations in thermal energy.

Conversely, the phase transitions of n-Nonadecane follow a distinct pathway. Originating as a liquid at higher temperatures, it undergoes a transformative shift to the R'I phase, marked by a distinct structural configuration. Subsequently, as the temperature continues to decrease, n-Nonadecane transitions into the Orthorhombic ( $\beta$ ) phase, denoting a specific crystalline arrangement of its molecular constituents. This intricate transition between liquid and crystalline phases underscores the nuanced behaviour of n-Nonadecane under varying thermal conditions. In essence, these observations emphasize the sensitivity of these substances to temperature variations, unveiling a rich tapestry of phase transitions governed by molecular intricacies.

The blue line in the graph represents the temperature profile of 1-Octadecanol as it transitions from the liquid phase to the R'IV phase under varying ratios of 1-Octadecanol to n-Nonadecane. Concurrently, the green line delineates the temperature trajectory of 1-Octadecanol during its phase transition from R'IV to the Monoclinic ( $\gamma$ ) phase. Meanwhile, the red line corresponds to the temperature curve of n-Nonadecane as it shifts from the liquid phase to the R'I phase. Lastly, the orange line illustrates the temperature progression of n-Nonadecane as it undergoes a phase transition from the R'I phase to the Orthorhombic ( $\beta$ ) phase.

Overall, due to the phase diagram, from high temperature to low temperature, the phase transitions of 1-Octadecanol are Liquid  $\rightarrow$  R'IV  $\rightarrow$  Monoclinic ( $\gamma$ ); [30] on the other hand, the phase transitions of n-Nonadecane are Liquid  $\rightarrow$  R'I  $\rightarrow$  Orthorhombic ( $\beta$ ) [27].




**Figure 10.** A binary system Phase Diagram of n-Nonadecane and 1-Octadecanol (Cooling) and Phases. Note: (•••) Thermal profile of 1-Octadecanol from the liquid state to the R'IV phase, observed across varied proportions of 1-Octadecanol to n-Nonadecane, (••••) Temperature trajectory of 1-Octadecanol during its phase transition from R'IV to the Monoclinic ( $\gamma$ ) phase, (•••) Temperature evolution of n-Nonadecane as it undergoes a phase shift from the liquid state to the R'I phase, (••••) Thermal progression of n-Nonadecane during its transition from the R'I phase to the Orthorhombic ( $\beta$ ) phase.

### 3.2.2. Heating Phase Diagram

In Figure 11, the blue trajectory delineates the thermal profile of 1-Octadecanol during its phase transition from the liquid state to the R'IV phase, observed across varied proportions of 1-Octadecanol to n-Nonadecane. Simultaneously, the red trajectory signifies the temperature evolution of n-Nonadecane as it undergoes a phase shift from the liquid state to the R'I phase. Furthermore, the orange trajectory graphically represents the thermal progression of n-Nonadecane during its transition from the R'I phase to the Orthorhombic ( $\beta$ ) phase.

Examining the Cooling and Heating Phase diagram allows for a discerning analysis of the phase transitions undergone by 1-Octadecanol. Notably, the transition from a stable phase to a rotator phase is evident. Intriguingly, during the heating process, this transition seems to dissipate (The region delineated by the green ellipse, comparing with Figure 10), suggesting that the disordered phase is not thermodynamically stable under elevated temperatures. Although a subtle phase transition is observable during heating, its intensity appears insufficient for accurate recognition by Differential Scanning Calorimetry (DSC). This implies that certain alterations in the molecular arrangement or energy state occur, but they might be subtle or transient, eluding detection by the precision of the DSC technique. This nuanced understanding of the phase behaviour of 1-Octadecanol sheds light on the intricacies of its thermodynamic stability and the sensitivity required in experimental methodologies to capture subtle transformations.



**Figure 11.** A binary system Phase Diagram of n-Nonadecane and 1-Octadecanol (Heating), Note: (•••) Thermal profile of 1-Octadecanol from the liquid state to the R'IV phase, observed across varied proportions of 1-Octadecanol to n-Nonadecane, (•••) Temperature evolution of n-Nonadecane as it undergoes a phase shift from the liquid state to the R'I phase, (•••) Thermal progression of n-Nonadecane during its transition from the R'I phase to the Orthorhombic ( $\beta$ ) phase, (○) Phase transitions undergone by 1-Octadecanol.

### 3.3. FTIR Spectra

The analysis of seven samples, as outlined in Table 1, involved the utilization of Fourier Transform Infrared (FTIR) spectroscopy. These samples, with varying compositions of 1-Octadecanol at 100%, 80%, 60%, 50%, 40%, 20%, and 0%, were selected for a comprehensive investigation.

The FTIR spectra obtained from these samples are visually represented below, offering valuable insights into the molecular composition. Figure 12 illustrates a spectrum comparing transmittance and wavenumber, while Figure 13, derived transformation from Figure 12 through OMNIC, depicts additional spectra comparing absorbance and wavenumber.

In the spectral analysis, distinctive peaks were identified, each corresponding to specific molecular vibrations. Notably, the peak observed around wavenumber  $750\text{ cm}^{-1}$  was attributed to the out-of-plane bending of the O-H bond. The peak at approximately  $1000\text{ cm}^{-1}$  indicated the stretching vibration of the C-O bond, while the peak around  $1500\text{ cm}^{-1}$  was associated with the bending vibration of the C-H bond. The double-peak evident around  $3000\text{ cm}^{-1}$  was identified as the saturated C-H stretching vibration absorption peak.

Of particular interest was the inconspicuous yet significant wide peak at around  $3300\text{ cm}^{-1}$ . This peak was attributed to the O-H stretching vibration associated with intermolecular hydrogen bonds. The presence and characteristics of these peaks provide valuable information about the molecular structure and interactions within the samples, contributing to a comprehensive understanding of the composition and behaviour of 1-Octadecanol in different proportions. This FTIR analysis serves as a crucial tool in unraveling the intricate details of the molecular dynamics of these samples and contributes to the broader understanding of their chemical properties [8].




Figure 12. FTIR spectra (Transmittance).




Figure 13. FTIR spectra (Absorbance).

#### 4. Results

To delve deeper into the complexities of the 1-Octadecanol and n-Nonadecane binary system, we observe a fascinating sequence of phase transitions that reveal the intricate nature of these compounds. For 1-Octadecanol, the transition begins in a liquid state, before transitioning to a R'IV phase, and finally stabilizing in a monoclinic structure. This progression demonstrates the compound's dynamic structural changes under varying conditions.

Similarly, n-Nonadecane exhibits its own unique transformation path. It starts from a liquid state and then moves into the R'I phase. Following this, it settles into an orthorhombic structure. This pathway underscores the distinct molecular behaviours of n-Nonadecane compared to 1-Octadecanol, even though they are part of the same binary system.

A particularly intriguing aspect of this study is the transition of 1-Octadecanol from the  $\gamma$ -phase to the rotator phase. This specific transition phase, which is of significant scientific interest, proves elusive when attempting to detect it using Differential Scanning Calorimetry (DSC). The challenge in detecting this transition lies in the extremely subtle nature of the signal that this phase change generates. It's a testament to the sensitivity required in measuring techniques and the need for precise instrumentation in the study of molecular phase transitions.

Moreover, the differences in the transition pathways of 1-Octadecanol and n-Nonadecane, despite being components of the same binary system, highlight the complexity and individuality of molecular structures and behaviours. These findings have broader implications for the study of phase transitions in binary systems, suggesting that even closely related compounds can exhibit markedly different behaviours under similar conditions. This complexity necessitates a more nuanced approach to the study of phase transitions in such systems, with a focus on the individual characteristics of each component as well as their interactions.

Drawing upon preceding research [31, 32], the Fourier-transform infrared (FTIR) analysis yielded valuable insights. Manifesting as a peak around the wavenumber  $750\text{ cm}^{-1}$ , the out-of-plane bending of the O-H bond was discerned. The peak encompassing  $1000\text{ cm}^{-1}$  signified the stretching vibration of the C-O bond, while the peak at  $1500\text{ cm}^{-1}$  denoted the bending vibration of the C-H bond. The distinctive double-peak discerned around  $3000\text{ cm}^{-1}$  was attributed to the saturated C-H stretching vibration absorption. Notably, an inconspicuous yet broad peak around  $3300\text{ cm}^{-1}$  was identified as the O-H stretching vibration indicative of intermolecular hydrogen bonds. These nuanced analytical findings contribute significantly to our understanding of the molecular dynamics and structural intricacies within this binary system, mirroring the complex nature of plant cuticle waxes.

## 5. Discussion

The Fourier-transform infrared (FTIR) analysis, based on previous studies, provided valuable insights into the molecular dynamics of Organic Polymer Functional Adsorption Materials. The identification of peaks at specific wavenumbers, such as  $750\text{ cm}^{-1}$  for the O-H bond bending,  $1000\text{ cm}^{-1}$  for the C-O bond stretching,  $1500\text{ cm}^{-1}$  for the C-H bond bending, and  $3000\text{ cm}^{-1}$  for the saturated C-H stretching vibration absorption, offered a detailed understanding of the material's composition. Additionally, the detection of a broad peak at  $3300\text{ cm}^{-1}$ , indicating O-H stretching vibration related to intermolecular hydrogen bonds, highlighted the complex molecular interactions within the binary system, akin to the intricate nature of plant cuticle waxes. Pascal. S [33] finds that the synthesis pathway of plant epidermal wax can be divided into three steps: 1) de novo synthesis of  $C_{16}$  and  $C_{18}$  fatty acids; 2)  $C_{16}$  and  $C_{18}$  fatty acids extend to form waxy synthesis precursors, namely VLCFAs; 3) Waxy components such as alkanes, aldehydes, ketones, primary alcohols, secondary alcohols, and wax esters are synthesized by VLCFAs through acyl reduction and decarboxylation pathways. The above synthesis process is completed in plant epidermal cells. The results of FTIR related research in this paper will play a supporting role in the synthetic waxy layer of plant epidermis.

Exploring the complexities of the 1-Octadecanol and n-Nonadecane binary system revealed a fascinating sequence of phase transitions, showcasing the dynamic structural changes of these compounds under varying conditions. 1-Octadecanol transitions from a liquid state to a R'IV phase before stabilizing in a monoclinic structure, while n-Nonadecane follows a unique transformation path from a liquid state to the R'I phase and eventually settling into an orthorhombic structure. These distinct molecular behaviours underscore the individuality of n-Nonadecane compared to 1-Octadecanol within the same binary system. Zhang [34] finds that different cuticle waxes can form different and reversible wax modifications, thus adjusting the water transpiration and adsorption properties of the leaf cuticle in response to the degree of water change in the soil. Skamnioti [35] finds that changes in cuticle permeability can affect plant disease resistance. Therefore, based on the phase transition path analysed in this paper, the plant epidermal wax layer modification can be artificially adjusted to improve the water transpiration and adsorption and disease resistance

properties of plants and emphasizing the diverse nature of Organic Polymer Functional Adsorption Materials.

**Author Contributions:** Conceptualization, Wentao. Guo. ; Yi. Xing. and Wei. Su. ; methodology, Wentao. Guo. ; software, Guotao. Li. ; validation, Changjiang. Hou. , Yi. Xing. and Wei. Su.; formal analysis, Wentao. Guo. ; investigation, Changjiang. Hou. ; resources, Yi. Xing. ; data curation, Wentao. Guo. ; writing—original draft preparation, Wentao. Guo. Guotao. Li. ; writing—review and editing, Wei. Su, Wei. Wen ; visualization, Guotao. Li. ; supervision, Yi. Xing, Wei. Wen ; project administration, Wentao. Guo. ; funding acquisition, Changjiang. Hou. All authors have read and agreed to the published version of the manuscript. Please turn to the CRediT taxonomy for the term explanation.

**Funding:** This work was supported by the National Key R&D Program of China (No. 2022YFE0208100), Key Research and Development Program of Hebei Province (No. 22373706D), Key Science and Technology Planning Project of HBIS Group Co., Ltd. (No. HG2020204-2), and Guangdong Province Engineering Laboratory for Air Pollution Control (20193236-09-06).

**Data Availability Statement:** All the data can be collected by contacting wentao\_guo@ustb.edu.cn.

**Acknowledgments:** The authors would like to express sincere gratitude to Prof. Kevin J. Roberts, Laksha Parameswaran, Alexander Jackson, and Yu Liu from University of Leeds for their continued assistance throughout the project, providing advice and guidance that was essential for completing this project.

**Conflicts of Interest:** The funders had no role in the design of the study; in the collection, analyses, or interpretation of data; in the writing of the manuscript; or in the decision to publish the results.

## References

1. Isaacson. T.; Kosma. D.; Matas. A.; Buda. G.; He. Y.; Yu. B.; Pravitasari. A.; Batteas. J.; Stark. R.; Jenks. M.; Rose. J. Cutin deficiency in the tomato fruit cuticle consistently affects resistance to microbial infection and biomechanical properties, but not transpirational water loss. *The Plant Journal* **2009**, 60(2), 363-377.
2. Jetter. R.; Riederer. M. Localization of the Transpiration Barrier in the Epi- and Intra-cuticular Waxes of Eight Plant Species: Water Transport Resistances Are Associated with Fatty Acyl Rather Than Alicyclic Components. *Plant Physiology* **2022**, 170, 921-934.
3. Lee. T.; Greenkorn. R.; Chao. K. Statistical thermodynamics of group interaction in n-alkane-n-alkanol and n-alkanol-n-alkanol solutions. *Chemical Engineering Science* 1973, 28(4), 1005-1011.
4. Anwar. M.; Turci. F.; Schilling. T. Crystallization mechanism in melts of short n-alkane chains. *The Journal of Chemical Physics* **2013**, 139(21), 214904.
5. Carey. Fa.; Giuliano. Rm.; Synthesis of 7,9-DI-O-Methyl-11-Oxosibirmoycinone; *Journal of Organic Chemistry* **1981**; Volume 46, 1366-1371.
6. Maissara. M.; Devaure. J.; Raman study of n-nonadecane and n-heneicosane mixtures in the solid state. *Journal of Raman Spectroscopy* **1987**, 18(6), 425-428.
7. Lehmler. H; Bergosh. R; Meier. M; Carlson. R; A novel synthesis of branched high-molecular-weight (C-40(+)) long-chain alkanes; *Bioscience Biotechnology and Biochemistry* 2002; 66; 523-531.
8. Ventolà, L.; Calvet. T.; Cuevas-Diarte. M.; Solans. X.; Mondieig. D.; Négrier. P.; van Miltenburg. J.; Solid state equilibrium in the n-alkanols family: the stability of binary mixed samples; *Physical Chemistry Chemical Physics* **2003**, 5(5), 947-952.
9. PubChem. <https://pubchem.ncbi.nlm.nih.gov/compound/8221> (accessed on 28 06 2022).
10. HSDB. <https://toxnet.nlm.nih.gov> (accessed on 16 07 2022).
11. Estimation of Henry's Law Constant for a Diverse Set of Organic Compounds from Molecular Structure. [https://cfpub.epa.gov/si/si\\_public\\_record\\_report.cfm?Lab=NERL&dirEntryId=191325](https://cfpub.epa.gov/si/si_public_record_report.cfm?Lab=NERL&dirEntryId=191325) (accessed on 06 08 2022).
12. Janardhanaiah, M.; Gangadhar. S.; Govinda. V.; Sreenivasulu. K; Venkateswarlu. P.; Effect of alkanol chain length on excess thermodynamic properties of p-cresol with 1-alkanol (C<sub>3</sub>-C<sub>8</sub>) at 298.15, 303.15, 308.15 and 313.15K; *Journal of Molecular Liquids* **2015**; 211; 169-177.
13. Dhanyalakshmi. K.; Soolanayakanahally. R.; Rahman. T.; Tanino. K.; Author 5, Nataraja. K.; Leaf Cuticular Wax, a Trait for Multiple Stress Resistance in Crop Plants;
14. [online] *Academia.edu* **2022**. [https://www.academia.edu/47867774/Leaf\\_Cuticular\\_Wax\\_a\\_Trait\\_for\\_Multiple\\_Stress\\_Resistance\\_in\\_Crop\\_Plants](https://www.academia.edu/47867774/Leaf_Cuticular_Wax_a_Trait_for_Multiple_Stress_Resistance_in_Crop_Plants) (Accessed 3 September 2022).
15. Buschhaus. C; Jetter. R.; Composition and Physiological Function of the Wax Layers Coating Arabidopsis Leaves:  $\beta$ -Amyrin Negatively Affects the Intracuticular Water Barrier; *Plant Physiology* **2012**, 160(2); 1120-1129.

16. Koch. K.; Barthlott. W.; Koch. S.; Hommes. A.; Wandelt. K.; Mamdouh. W.; De-Feyter. S; Broekmann. P.; Structural analysis of wheat wax (*Triticum aestivum*, c.v. 'Naturastar' L.): from the molecular level to three dimensional crystals; *Planta* 2005, 223(2); pp.258-270.
17. Van Maarseveen. C.; Han. H.; Jetter. R.; Development of the cuticular wax during growth of *Kalanchoe daigremontiana* (Hamet et Perr. de la Bathie) leaves; *Plant, Cell, and Environment* 2009; 32(1); 73-81.
18. Riederer. M.; Muller. C.; Biology of the Plant Cuticle; *Annual Plant Reviews* 2006; Volume 23.
19. Yeats. T.; Rose. J.; The Formation and Function of Plant Cuticles; *Plant Physiology* 2013; 163(1); 5-20.
20. Koornneef. M.; Hanhart. C.; Hilhorst. H.; Karssen. C.; In Vivo Inhibition of Seed Development and Reserve Protein Accumulation in Recombinants of Abscisic Acid Biosynthesis and Responsiveness Mutants in *Arabidopsis thaliana*; *Plant Physiology* 1989; 90(2); pp.463-469.
21. Yong-Hwan Lee. R.; Hydrophobicity of contact surface induces appressorium formation in *Magnaporthe grisea*. *FEMS Microbiology Letters* 1994; 115(1); 71-75.
22. Gilbert. S.; Opitz. J.; Raff. R.; Resynthesizing Evolutionary and Developmental Biology. *Developmental Biology* 1996, 173(2), 357-372.
23. Bessire. M.; Chassot. C.; Jacquat. A.; Humphry. M.; Borel. S.; Petétot. J.; Métraux. J.; Nawrath. C.; A permeable cuticle in *Arabidopsis* leads to a strong resistance to *Botrytis cinerea*; *The EMBO Journal* 2007; 26(8); pp.2158-2168.
24. Delventhal. R.; Falter. C.; Strugala. R.; Zellerhoff. N.; Schaffrath. U.; Ectoparasitic growth of *Magnaporthe* on barley triggers expression of the putative barley wax biosynthesis gene CYP96B22 which is involved in penetration resistance. *BMC Plant Biology* 2014, 14(1).
25. Hen-Avivi. S.; Savin. O.; Racovita. R.; Lee. W.; Adamski. N.; Malitsky. S.; A Metabolic Gene Cluster in the Wheat W1 and the Barley Cer-cqu Loci Determines  $\beta$ -Diketone Biosynthesis and Glauconsness. *The Plant Cell* 2016; 28(6); 1440-1460.
26. Heredia-Guerrero. J.; Ben-Átez. J.; Dom-Ánguez. E.; Bayer. I.; Cingolani. R.; Athanassiou. A.; Heredia. A.; Infrared and Raman spectroscopic features of plant cuticles: a review; *Frontiers in Plant Science* 2014; 5.
27. Liu. J.; Sheng. L.; Xu. Y.; Li. J.; Yang. Z.; Huang. H.; Xu. L.; WOX11 and 12 Are Involved in the First-Step Cell Fate Transition during de Novo Root Organogenesis in *Arabidopsis*; *The Plant Cell* 2014; 26(3); 1081-1093.
28. Dirand. M.; Bouroukba. M.; Chevallier. V.; Petitjean. D.; Behar. E.; Ruffier-Meray. V. Normal Alkanes, Multialkane Synthetic Model Mixtures, and Real Petroleum Waxes: Crystallographic Structures, Thermodynamic Properties, and Crystallization. *Journal of Chemical and Engineering Data* 2002, 47(2), 115-143.
29. Miquel. Àngel. Cuevas-Diarte.; Y. Haget.; N. B. Chanh.; H. A. J. Oonk. *Molecular Mixed Crystals*, 1st ed.; Publisher: Springer Nature Switzerland AG Gewerbstrasse 11, 6330 Cham, Switzerland, 2021; Volume 3, pp. 9-46.
30. Cholakov. D.; Denkov. N. Rotator phases in alkane systems: In bulk, surface layers and micro/nano-confinements. *Advances in Colloid and Interface Science* 2019, 269, 7-24.
31. Cuevas-Diarte, M. and Oonk, H., n.d. *Molecular Mixed Crystals*.
32. G. P. Hastie; K. J. Roberts. Investigation of inter- and intra-molecular packing in the solid state for crystals of normal alkanes and homologous mixtures using FT-IR spectroscopy. *Journal of Materials Science* 1994, 1915-1919.
33. Gorce, J.; Spells, S.; FTIR studies of conformational disorder: crystal perfecting in long chain n-alkane; *Polymer* 2004; 45, 3297-3303.
34. Pascal. S, Bernarda, Deslous. P., *Arabidopsis CER1-LIKE1* functions in a cuticular very-long-chain alkaneforming complex [J]. *Plant Physiology*, 2019, 179( 2) : 416.
35. Zhang. Y., Study on the correclation between cuticular wax composition and cuticular transpiration in *Camellia Sinensis* leaves. [D] Fujian Agriculture and Forestry University, 2021, DOI: 10.27018/d.cnki.gfjnu.2020.000036, Supervisor: Chen M.J., and Chen C.S., pp.51-67.
36. Skamnioti. P, Gurr. S. J., *Magnaporthe grisea* cutinase 2 mediates appressorium differentiation and host penetration and is required for full virulence [J]. *The Plant Cell*, 2007, 19 (8): 2674.

**Disclaimer/Publisher's Note:** The statements, opinions and data contained in all publications are solely those of the individual author(s) and contributor(s) and not of MDPI and/or the editor(s). MDPI and/or the editor(s) disclaim responsibility for any injury to people or property resulting from any ideas, methods, instructions or products referred to in the content.